


REV	DATE	MODIFICA	DRAWER
0	14/10/2008	FIRST ISSUE	GM



Material List of Drw: 12834 - 1140

Title: ADJUSTABLE ACCENTRIC BUSH APPLICATION

Ref. Drv 12834 - 1000 Ref. Pos: 6

Item\Fam: 0400 Groups for crane: 16

Material Handling Engineering																	
<div><div><div>Data: 03-lug-09</div><div>Project: 12834</div><div>Job: 18033</div><div>Mat List of Drw: 1140</div><div>Ref. Drw: 1000 - 12834</div><div>Ref. Pos: 6</div><div>Item\Fam : 0400</div><div>Groups for crane: 16</div></div><div><div>Customer: PIRAEUS PORT AUTHORITY - RMG 40t</div><div>Title: ADJUSTABLE ACCENTRIC BUSH APPLICA</div></div></div>																	
POS	DRW N°	ELECTRICAL CODE	DESCRIPTION	MATERIAL	NOTE FUNCTION	DIMENSIONS	Qty in Drw	Weight in Drw	Qty for 1 Crane	Qty for Job	RAM	ORD	SUPPLIED BY	MADE BY	ITEM	FAM	REV
1	12834 - 1141		BOGIE PIN	C45 E +QT-EN10083-1 or Equivalent	QUENCHING & TEMPERING	DIA130x566	1	57	16	128					04	04	
2	12834 - 1142		BUSH	S355JO or Equivalent		DIA170x55	2	6	32	256					04	04	
3	12834 - 1143		ECCENTRIC BUSH	S355JO or Equivalent		DIA211,9x98	2	34	32	256					04	04	
4	12834 - 1144		LOCKING PLATE	S355JO or Equivalent			4	7	64	512					04	04	
5	12834 - 1140		WELDED PLATE	S355JO or Equivalent	PL20	70x30	2	0,5	32	256					04	04	
6	12834 - 1140		SCREW	8.8	HOT DIP GALVANIZED	DIN933/ISO 4017 M20x55	8	1,5	128	1024					04	81	
7	12834 - 1140		WASHER	C70	HOT DIP GALVANIZED	DIN127 di=21	8		128	1024					04	81	
8	12834 - 1140		GREASE NIPPLE		SPHERICAL HEAD	1/4" Gas	2		32	256					04	81	
WEIGHT FOR CRANE [kg]: 1696																	