


REV	DATE	MODIFICA	DRAWER
00	11/02/2009	FIRST ISSUE	TM
01	06/03/2009	GENERAL REVISION	TM
02	31/03/2009	REVISED POS.18, 20, ADDED POS.25-33 DELETED POS.15	LD



Material List of Drw: 12834 - 5201

Title: COLUMNS

Ref. Drv5201 - 12834Ref. Pos: 1

Item\Fam: 0606Groups for crane: 1

Material Handling Engineering																	
				Data: 03-lug-09	Project: 12834	Job: 18033	Mat List of Drw: 5201	Ref. Drw: 12834 - 5201	Ref. Pos: 1	Item\Fam : 0606	Groups for crane: 1						
				Customer: PIRAEUS PORT AUTHORITY - RMG 40t	Title: COLUMNS												
POS	DRW N°	ELECTRICAL CODE	DESCRIPTION	MATERIAL	NOTE FUNCTION	DIMENSIONS	Qty in Drw	Weight in Drw	Qty for 1 Crane	Qty for Job	RAM	ORD	SUPPLIED BY	MADE BY	ITEM	FAM	REV
1	12834 - 5201		PLATE	S235JR or equivalent	PL20	430x430	1	29	1	8					06	06	00
2	12834 - 5201		PLATE	S235JR or equivalent	PL12	484x2458	2	224	2	16					06	06	00
3	12834 - 5201		PLATE	S235JR or equivalent	PL6	128x150	8	7,2	8	64					06	06	00
4	12834 - 5201		PLATE	S235JR or equivalent	PL25	430x430	1	36,3	1	8					06	06	00
5	12834 - 5201		PLATE	S235JR or equivalent	PL20	340x340	3	54	3	24					06	06	00
6	12834 - 5201		PLATE	S235JR or equivalent	PL20	220x260	3	27	3	24					06	06	00
7	12834 - 5201		PROFILE	S235JR or equivalent	HEA 220	2483	3	375	3	24					06	06	00
8	12834 - 5201		PROFILE	S235JR or equivalent	HEA 220	3467	2	350	2	16					06	06	00
9	12834 - 5201		PLATE	S235JR or equivalent	PL20	290x260	4	47,2	4	32					06	06	00
10	12834 - 5201		PLATE	S235JR or equivalent	PL20	340x275	4	56	4	32					06	06	00
11	12834 - 5201		PLATE	S235JR or equivalent	PL6	90x188	18	14,4	18	144					06	06	00
12	12834 - 5201		PLATE	S235JR or equivalent	PL6	100x130	4	2,4	4	32					06	06	00
13	12834 - 5201		PLATE	S235JR or equivalent	PL6	100x105	4	1,9	4	32					06	06	00
14	12834 - 5201		PROFILE	S235JR or equivalent	HEA 220	3448	2	348	2	16					06	06	00
16	12834 - 5201		PROFILE	S235JR or equivalent	UPN 180	4595	4	404	4	32					06	06	00
17	12834 - 5201		PLATE	S235JR or equivalent	PL6	164x85	22	14	22	176					06	06	00
18	12834 - 5201		PLATE	S235JR or equivalent	PL6	170x108	22	13,7	22	176					06	06	02
19	12834 - 5201		PLATE	S235JR or equivalent	PL6	180x133	6	6,7	6	48					06	06	00
20	12834 - 5201		PROFILE	S235JR or equivalent	UPN 180	3410	2	150	2	16					06	06	02
21	12834 - 5201		PROFILE	S235JR or equivalent	UPN 180	3850	2	169	2	16					06	06	00
22	12834 - 5201		PROFILE	S235JR or equivalent	UPN 180	3765	2	165,5	2	16					06	06	00

Material Handling Engineering			Data: 03-lug-09		Project: 12834		Job: 18033		Mat List of Drw: 5201		Ref. Drw: 12834 - 5201		Ref. Pos: 1		Item\Fam : 0606		Groups for crane: 1	
			Customer: PIRAEUS PORT AUTHORITY - RMG 40t				Title: COLUMNS											
POS	DRW N°	ELECTRICAL CODE	DESCRIPTION	MATERIAL	NOTE FUNCTION	DIMENSIONS	Qty in Drw	Weight in Drw	Qty for 1 Crane	Qty for Job	RAM	ORD	SUPPLIED BY	MADE BY	ITEM	FAM	REV	
23	12834 - 5201		PLATE	S235JR or equivalent	PL6	180x108	12	10,8	12	96					06	06	00	
24	12834 - 5201		PLATE	S235JR or equivalent	PL6	90x108	4	1,8	4	32					06	06	00	
25	12834 - 5201		PLATE	S235JR or equivalent	PL20	180x180	2	10	2	16					06	06	02	
26	12834 - 5201		PLATE	S235JR or equivalent	PL20	440x1240	1	75	1	8					06	06	02	
27	12834 - 5201		PLATE	S235JR or equivalent	PL20	380x1240	1	69	1	8					06	06	02	
28	12834 - 5201		PLATE	S235JR or equivalent	PL12	502x580	2	50	2	16					06	06	02	
29	12834 - 5201		PLATE	S235JR or equivalent	PL12	197x890	2	19	2	16					06	06	02	
30	12834 - 5201		PLATE	S235JR or equivalent	PL12	170x890	2	19	2	16					06	06	02	
31	12834 - 5201		PLATE	S235JR or equivalent	PL8	DIA 200	2	3,2	2	16					06	06	02	
32	12834 - 5201		PLATE	S235JR or equivalent	PL8	144x200	2	3,2	2	16					06	06	02	
33	12834 - 5201		PLATE	S235JR or equivalent	PL8	160x200	2	3,2	2	16					06	06	02	
WEIGHT FOR CRANE [kg]: 2759,5																		