

Date: 16/05/2025

Technical Specifications for the waiting seats (3-seater metallic sofas)

1. Procurement and installation of thirty-six (36) items of metallic waiting seats (sofas) for outdoor use, three seaters, galvanized, with armrests, without a small table (Material: Galvanized Steel).
2. Indicative dimensions: 1900X700X800mm, with a dimensions' tolerance of approximately 10%.
3. Each seat's width should be 52 cm. The height of the seat surface from the ground should be 43 cm. The height of the backrest from the ground should be 80 cm.
4. The seats to be supplied should be of excellent quality, new, and unused, in silver, platinum, or metallic gray color. All metal parts of the seats should undergo degreasing, derusting, phosphating processes, and should be painted with epoxy electrostatic oven coat.
5. The waiting seats should be functional, durable, and flexibly designed for specific use namely: extended stay, waiting and use of the public and should be of elegant aesthetics. At the same time, the seats should consist a sturdy construction of a big life cycle, with great resistance to weather conditions near the sea.
6. All seats must be suitable for being fixed to the ground. The grounding work will be carried out under the supervision of the competent PPA S.A. department.
7. The collaborating parts (if any) should be intercompatible and interchangeable, with easy access and replacement of the main parts. The assembly of the above parts should be easy and quick, adaptable to the special needs and specificities of each space, providing flexibility, ease of maintenance, restoration, and cleaning.
8. An undivided perforated seat and backrest that leaves a border of a non-perforated surface around the perimeter for aesthetic reasons. The design should be anatomically shaped.

9. Required certificates for compliance with quality standards, final products, and tests of the offered items from accredited bodies.
10. The delivery and installation of the metal seats will be carried out at the Central Port of Piraeus in locations indicated to the awarded Contractor. The total time for delivery and installation should not exceed 15 calendar days from the assignment of the procurement.